



TYPICAL CONTROL TERM STRIP CABINET
NOT TO SCALE

- NOTES:
1. FOR NUMBER AND SIZE FOR CONDUIT AND CABLE SEE DRAWING E1-02.
 2. UPS MODULE SHALL BE LEIBERT MODEL MAX OUTPUT 120VAC.
 3. UPS INSTALLATION SHALL INCLUDE EQUIPMENT WITH SLIDE RAILS OR BRACKETS ATTACHED AT WALL MOUNTED SHELF MOUNT UPS POWER STRIP CABINET AND CONNECTED TO GROUND IN THE STRIP CABINET.